



BAY VILLAGE

High specification, aesthetically pleasing accommodation units were manufactured and installed by ATCO, to accommodate Woodside's transient workforce.

The buildings were designed in a pod arrangement, containing accommodation, accessible accommodation and laundry units. ATCO met the required production schedule, consistently completing four complete pods (16 buildings) per week to ensure the time sensitive installation schedule could be met.

High specification materials were selected to exceed the usual construction camp finishes, and in order to elevate both appearance and durability.



PROJECT FEATURES

- ❖ (104) double storey accommodation units, to accommodate four people.
- ❖ Custom engineered footings were required for site and installed insitu.
- ❖ Verandas and stairs were designed to meet the demands of Karratha's cyclonic season.
- ❖ ATCO delivered this project to the required timeframes and to budget, even despite a cyclone occurring during installation.

