

# Gold Coast University Hospital Site Office

Construction



Bovis Lendlease requested a modular building with high specification interior to be used as the administration team office for the Gold Coast University Hospital construction project in Southport, Queensland.

ATCO designed, manufactured, and installed, a two storey modular office building with a total footprint size of 1,879 m<sup>2</sup> comprised of private and open-plan offices, meeting rooms, reception area, lunch rooms, and bathroom amenities.

To meet the request for a high specification interior, ATCO incorporated suspended ceiling tiles, glazed wall partitions, cushion tac carpet, commercial grade vinyl flooring, commercial fittings and finishes on cabinetry, and internal stair access. To meet sustainability request, energy efficient lighting and air-conditioning where also included in the design.

The turnkey installation included electrical fit out and plumbing reticulation to battery limit. In addition to this high specification modular building, ATCO provided 150 various site offices and amenities to support the construction project team.

## Snapshot

**Location:** Southport, Qld

**Date:** December 2009

**Client:** Bovis Lendlease

### Features:

- » 26.1 m x 36 m double storey complex
- » High specification fit out
- » Energy efficiency solutions